5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work.	*Per.*	*Quantity*
Earthwork excavation	C. yd	13,040
Concrete in mortar	C. ft	21,097
Burnt stone in mortar with bond stones 6" apart	„	53,463
Old stone in mortar with new bond stones 6' apart	„	1,312
Burnt stone slabs 6" thick	S. ft.	7,138
Old stone slabs 6" removing and relaying	„	1,181
Burnt stone slabs 4" thick dressed	„	2,918
Old stone slabs removing and relaying	„	451
Flooring with stone slabs 3" thick and pointed	„	3,775
Collecting and spreading sand	C. yd.	26
Pointing with surki mortar	Sqr.	388·74
Burnt stone work dry	C yd.	858
Blasting rock	„	150
Guard stones dressed	Each	28
Dismantling stone masonry work	C. ft.	1,968
Adding 1 vent 4½' × 3' to the existing tunnel on Gavipur road and repairing present vent	Lump sum	Rs.
Barricading and lighting charges	„	„
Forming road surface, metalling the disturbed portion, and forming banks for the earthen channel	„	„
Repairing and resetting footpath tunnel	„	„
Compensation for lands under Chikkere tank and other portions	„	„
Cutting trees and clearing jungle, etc.	„	„

J. BUCHE,
Sanitary Engineer.

HASSAN DIVISION.

Dated 6th March 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 22nd March 1911, for improving and extending the Executive Engineer's Office at Hassan. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1911.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. to 5 P.M.

3 Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving and extending the Executive Engineer's Office at Hassan," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities.

Items.	*Per.*	*Quantity.*
Dismantling brick masonry	C. ft.	279
Do Cuddapah slabbed flooring	Sqr.	·44
Do the existing windows without damaging ...	Lump sum.	
Earthwork excavating foundation	C. yds.	46
Do filling in basement	do	41
Stone in chunam foundation and basement	C. ft.	1 740
Burnt brick in chunam	do	3,780
Do arch work	do	82
Centring for the arch work	Lump sum.	
Burnt stone slabs 6" thick, dressed	S. ft.	281
Plastering with chunam	Sqr.	52·98
Whitewashing, two coats	do	122·42
Color-washing, two coats	do	63·37
Flooring with Cuddapah slabs on 3" concrete	do	7·83
Rectifying the Cuddapah slabbed flooring of the extended room.	Lump sum.	
Teakwood work wrought and put up with oiling	C. ft.	68
Iron truss complete	No.	3
Roofing with Mangalore tiles on teak reepers	Sqr.	14·79
Ridging with Mangalore tiles	R. ft.	51
Teakwood eave board	do	160
Zinc gutter including fixing, complete	do	102
Teakwood panelled door with hinges, bolts, etc., complete ...	S. ft	72
Do ½ panelled and ½ glazed	do	72
Do windows inside glazed and outside panelled shutters with iron bars	do	213
Do screen with ½ panelled and ½ glazed door, complete ...	do	162
Painting doors and windows	Sqr.	9·92
Oiling the wood work inside doors and windows and ventilators ...	do	25·00
Pointing with chunam the basement	do	2·92
Horbury's patent, latrine of 3 seats with sanitation pipe, etc., with carriage and fixing, etc., complete	Lump sum.	
Dismantling the existing delapidated building	do	

V. AIYASWAMI IYER,
Executive Engineer